


APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/08/2013-14, Date: 11.07.2013

Improvements of roads and drains Bhadrappa layout in ward no. 08, Kodigehalli sub division. (Change of work: Drilling of borewells at Maruthi nagara and Devinagara in ward no. 08, Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				SRINIVAS H G	
				In Figures	In Words
1	2	Geophysical survey geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the hand pumps, MWS or PWSS by vertical electrical sounding by adopting verner or schlumbergers's method including reconnaissance survey of geological formation Geophysical investigation of existing ground Water in the vicinity. its quality , quality & acceptability of the users indicating the location of the site recommended depth of casing pipe required to seal the tope unconsolidated formation including an extra depth 1.0 metre in consolidated formation for aquire proposed to be tapped propable yield and other information required including transportation of instrument and accessories to work site, engating technical personal and labour etc.,PRE- Bangalore Circle-2011-12, Page No-43, Item No-9.4	Each	1994.81	Rupees One Thousand Nine Hundred Ninety Four and Eighty One Paise Only
2	100	Sinking of Borewell of 165 mm clear using fast hydraulic rig of capacity 250 PSIG & above 900 CMF & abpve in al strata including over burden upto 22 m fixing of casing pipes, collars and cap with necessary cutting and threading including transporation of rig and surpporting vehicles, screws charges and cost of consumable including yield testing at the final depth with a minimum working of compressor for one hour all as specified.,PRE- Bangalore Circle-2011-12, Page No-43, Item No-9.4 0.00 to 50.00 mtrs	Rmtr	301.32	Rupees Three Hundred One and Thirty Two Paise Only
3	100	50mtr to 100.00 mtr	Rmtr	397.91	Rupees Three Hundred Ninety Seven and Ninety One Paise
4	100	100.00 to 150.00 mtr	Rmtr	443.06	Rupées Four Hundred Forty Three and Six Paise Only
5	100	150.00 to 200.00 mtr	Rmtr	487.15	Rupees Four Hundred Eighty Seven and Fifteen Paise Only
6	100	200.00 to 250.00 mtr	Rmtr	538.60	Rupees Five Hundred Thirty Eight and Sixty Paise Only
7	100	250.00 to 300.00 mtr	Rmtr	577.45	Rupees Five Hundred Seventy Seven and Forty Five Paise Only
8	80	Supply of ISI Mark 175mm Nominal bore ,plain end steel Casing pipe-grade of steel Fee 410 of wall thickness 5.4 mm thick confirming to IS 1387/1933 and manufactured by basic open hearth electric or basic oxygen process in random lenth of 5 to 7mtrs. Both ends threaded Confirming to IS 554/1985, One end fixed with a Socket Confirming to IS 4270:2001 and the other end with Screwed pipes . All pipes shall be reasonably free from defectes. The tube shall be reasonably straight should be with ISI marking, weighing 25.10kg/mtr. (Inclusive of all taxes) (PRED,2010-11 Page No.II item No-54) Casing pipe	Rmtr	1391.12	Rupees One Thousand Three Hundred Ninety One and Twelve Paise Only
9	20	Additional rate on item No. 2 is allowed for drilling in over burden and folling casing pipes beyond 20mtrs, rate at 15% and beyond 30mtrs 30% on basic rate of Rs.287 is allowed (PRED,2010-11 Page NoII item No-9.4) Above 20 mtrs and Upto 30 mtrs at	Mtr	45.20	Rupees Forty Five and Twenty Paise Only
10	20	Above 30 mts	Mtr	90.40	Rupees Ninety and
11	22	Providing 175 mm dia MS Collar (RDED SR page ii, item55)	Each	157.49	Rupees One Hundred Fifty Seven and Forty Nine Paise Only
12	2	Providing 175 mm dia MS Cap(as per RDED SR page ii, item-54)	Each	104.99	Rupees One Hundred Four and Ninety Nine



Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				SRINIVAS H G	
				In Figures	In Words
13	2	Supply and delivery at site brand new Texmo / Innoval / Lubi / Sabar / Atalanta / Calamal / waterman / Radha make suitable vertical installation in 150mm dia. Borewells comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3Ph., 50Hz. 380/440 volts AC supply fitted with required accessories such as suction. casing, suction strainers, sand guard Non return valve etc., complete the pump and motor shall form an integral unit with all the required fittings 15HP 30 stage SE Approved Rate Letter No:2133 date :30/07/2010	No	54594.80	Rupees Fifty Four Thousand Five Hundred Ninety Four and Eighty Paise Only
14	592	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgin PVC insulation and Sheated Suitable for working Voltage Upto 1100 Volts as per Page No:49 item No 29C/1 PREE- SR 2011-12	Mtr	158.53	Rupees One Hundred Fifty Eight and Fifty Three Paise Only
15	2	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specification (As Per Rate approved By SE, RDED, Letter No.2081/2010-11 Dt:28-07-2010)	No	1606.35	Rupees One Thousand Six Hundred Six and Thirty Five Paise Only
16	2	Supplying and fixing 50mm GM GaTe Vavle (As Per Rate approved by SE, RDED, Letter No.2081/2010-11 Dt: 28-07-2010)	No	1501.36	Rupees One Thousand Five Hundred One and
17	2	Supplying and fixing 160mm Borewell cap with clampset (As Per Rate approved by SE, RDED, Letter No.2081/2010-11 Dt: 28-07-2010)	No	724.43	Rupees Seven Hundred Twenty Four and Forty Three Paise
18	2	Supplying and fixing 50mm GI Union (As Per Rate approved by SE, RDED, Letter No.2081/2010-11 Dt: 28-07-2010)	No	257.23	Rupees Two Hundred Fifty Seven and Twenty Three Paise
19	4	Supplying and fixing 50mm GI Elbow (As Per Rate approved by SE, RDED, Letter No.2081/2010-11 Dt: 28-07-2010)	No	125.99	Rupees One Hundred Twenty Five and Ninety Nine Paise
20	68	Supplying and fixing 50mm GI collar Heavy duty	No	1417.37	Rupees One Thousand Four Hundred Seventeen and Thirty Seven
21	2	Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp (As per rate approved by SE, RDED, Letter No-2133/2010-11 DT: 30-07-2010)	No	10499.00	Rupees Ten Thousand Four Hundred Ninety Nine Only
22	420	Providing and fixing of 50mm G.I pipe 'C' class heavy duty foe erection of submersible pumpset (As per BWSSB Store Issued Rate)	Mtr	422.85	Rupees Four Hundred Twenty Two and Eighty Five Paise
23	2	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., complete (As Per Rtae Approved by CE, RDED, Letter No-8650/2003-01 Dt: 8-3-2004)	No	498.70	Rupees Four Hundred Ninety Eight and Seventy Paise Only
24	2	Supplying of TPST with rewirable porcelain channels in SM encloser 15/32 amps P-346, i-1.(a), BWSSB SR 2008-09.	No	1417.37	Rupees One Thousand Four Hundred Seventeen and Thirty Seven
25	2	Supplying and fixing 500x500x65mm polished wood board made up not less than 15mm thick plank in front plank one end provided for olding at other end fixing the same of the valve using through bolts and nuts, P-346, I-2(f), BWSSB SR 2008-09.	No	288.72	Rupees Two Hundred Eighty Eight and Seventy Two Paise Only
26	6	Supplying and fixing LED Type panel board indicating lamp with required colour suitable for 220 v AC 50Hz 12/24 V DC Group 'B'. P-354, I-35(b), BWSSB SR 2008-09.	No	367.47	Rupees Three Hundred Sixty Seven and Forty Seven Paise

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				SRINIVAS H G	
				In Figures	In Words
27	40	Supplying and drawing each PVC insulated 650/100 V grade wire in the conduct (Open or Concealed system of wiring) 7/20 or 7/36 copper wire. P-332, I-20, ii(d), BWSSB SR 2008-09.	No	26.25	Rupees Twenty Six and Twenty Five Paise Only
28	2	Supplying, fixing and wiring heavy duty low voltage capacitors conforming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity P-354, I-34(a), BWSSB SR 2008-09.	No	367.47	Rupees Three Hundred Sixty Seven and Forty Seven Paise Only
29	2	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required P-350, I-13 (E, a), BWSSB SR 2008-09.	No	1128.64	Rupees One Thousand One Hundred Twenty Eight and Sixty Four Paise
30	2	and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.50m long buried in a pit. The pit should be filled with equal proportion of silt and charcoal 150mm around the pipe to complete depth. the connection from the pipe to the conduct etc., is to be established through GI wire of size as per ISI specifications 7.3.3 IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122mm dia P-377, I-7, BWSSB SR 2008-09.	No	1574.85	Rupees One Thousand Five Hundred Seventy Four and Eighty Five Paise Only
31	20	Supplying and fixing class A (medium duty) GI pipe wall thickness not less than 3.25mm on pole.	No	230.98	Rupees Two Hundred Thirty and Ninety Eight Paise Only
32	70	Supply 1.1 KV class UG cable from nearest BESCO pole to panel board including earth work and road restoratio 4 core 16 sqmm. P-378, I-10(d), BWSSB SR 2008-09.	Mtr	157.49	Rupees One Hundred Fifty Seven and Forty Nine Paise Only
33	70	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., complete P-379, I-12 (b), BWSSB SR 2008-09.	Mtr	5.25	Rupees Five and Twenty Five Paise Only
34	60	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled with neccesary bitumen / insulating compound complete with termiinalas, clamps, bolts, nuts, washers etc., P-380, I-16(b), BWSSB SR 2008-09.	No	52.50	Rupees Fifty Two and Fifty Paise Only
35	2	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled with neccesary bitumen / insulating compound complete with termiinalas, clamps, bolts, nuts, washers etc., P-380, I-16(b), BWSSB SR 2008-09.	No	251.98	Rupees Two Hundred Fifty One and Ninety Eight Paise Only
36	12	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using neccesary nuts, bolts and washers etc., complete P-32, I-3 (b), PWD ELECTRICAL SR 2010-11.	No	229.93	Rupees Two Hundred Twenty Nine and Ninety Three Paise
37	4.5	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. (Pg. No-267, I.No-37.38)	cum	249.29	Rupees Two Hundred Forty Nine and Twenty Nine Paise Only
38	4.5	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Cement concrete road. (Pg. No-267, I.No-37.40)	cum	521.95	Rupees Five Hundred Twenty One and Ninety Five Paise Only
39	9	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-5, I.No2.4)	cum	208.11	Rupees Two Hundred Eight and Eleven Paise Only
40	140	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc., complete PVC pipes of 6kg/Sqm 75mm Dia.(Page NO-14, ITEM no-3.4.2 (b), of PRE SR 2011-12).	Rmtr	122.84	Rupees One Hundred Twenty Two and Eighty Four Paise Only
41	9	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour complete as per specification. (Pg. No-6, I.No-2.11)	cum	55.64	Rupees Fifty Five and Sixty Four Paise Only
42	9	Disposing of excavated earth to the final place of disposal with all lead and lift and as directed by the Engineer in charge of the work. (Lead up to 15.00 KM)	cum	112.18	Rupees One Hundred Twelve and Eighteen Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				SRINIVAS H G	
				In Figures	In Words
43	2	Transportation of pumping machineries	no	892.42	Rupees Eight Hundred Ninety Two and Forty Two Paise
44	1	Erection of Pumping machineries	no	892.42	Rupees Eight Hundred Ninety Two and Forty Two Paise



Signature of the Contractor



Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92